

02 — Scope of Work

1. Site Preparation & Earthworks

Clearing and grubbing of 2,200 sq. m. site. Bulk excavation to depth of 12.5 m for 3-level basement. Dewatering system installation and operation throughout excavation phase. Shoring and retaining wall construction using secant pile wall system (600 mm dia. piles, 18 m depth). Disposal of approximately 27,500 cubic meters of excavated material off-site.

2. Foundation Works

Raft foundation design with thickness of 1,200 mm, covering full basement footprint. Concrete grade C-40, 50 mm cover to reinforcement. Anti-termite treatment and waterproofing membrane (APP modified bitumen, 4 mm thick) across entire raft. Pile caps where applicable per structural engineer's design.

3. Basement Construction (B3–B1)

3 levels of basement using post-tensioned flat-slab system (250 mm slab). Basement walls in 250 mm thick RCC. Waterproofing of basement walls and floors using crystalline waterproofing admixture plus external membrane. Car parking for 380 vehicles across 3 levels.

4. Superstructure (G+22)

Structural system: RCC moment-resisting frame with shear wall core. Column sizes vary from 900x900 mm at lower floors to 500x500 mm at upper floors. Typical floor slab: 200 mm flat plate. Building total height: 96 meters. Floor-to-floor height: 3.6 m typical, 5.0 m at ground level.

■■ INTENTIONAL CONFLICT: The Scope of Work states 380 car parking spaces across 3 basement levels. However, the BOQ (Section 05) lists quantities for 340 parking stalls. Bidders should seek clarification before submission.

5. Facade Works

Double-skin unitized curtain wall system with Low-E glazing (6+12+6 mm double-glazed units). Powder-coated aluminum framing in charcoal grey finish. Total glazed facade area: approximately 28,000 sq. m.

6. Internal Finishes (Shell & Core)

Screed and concrete topping to all floors. Lift lobbies with granite flooring and gypsum board ceiling. Toilets fully fitted with imported sanitary ware. Office floors delivered as shell & core (raised access floor by tenant). Ground floor retail finished to a high-end specification.