

High-Rise Commercial Tower (G+22)

Tender Reference: TND-2026-00002 | Issued by: Skyline Developments Pvt. Ltd.

05 — Bill of Quantities (BOQ)

Note: Quantities are engineer's estimates. Bidders must verify all quantities against drawings. Rate to be quoted in PKR per unit. Total = Qty x Rate (to be filled by bidder).

#	Description	Unit	Qty	Rate (PKR)	Total (PKR)
1	Bulk Excavation (to B3 level, 12.5 m depth)	m3	27,500	—	—
2	Secant Pile Wall (600 mm dia., 18 m depth)	m	3,200	—	—
3	Raft Foundation Concrete C-40 (1,200 mm avg.)	m3	2,640	—	—
4	Raft Foundation Reinforcement (Grade 60)	Ton	380	—	—
5	Basement Slab C-35 (Post-Tensioned, 250 mm)	m3	1,980	—	—
6	Basement Wall RCC C-35 (250 mm)	m3	720	—	—
7	Car Parking Provision — Basement (■ 340 stalls listed vs 380 in Scope)		340	—	—
8	Superstructure Column Concrete C-35/C-30	m3	4,200	—	—
9	Superstructure Column Reinforcement	Ton	820	—	—
10	Flat Plate Slab C-30 (200 mm, Floors G–22)	m3	6,800	—	—
11	Slab Reinforcement	Ton	1,050	—	—
12	Shear Wall RCC (all levels)	m3	1,450	—	—
13	Curtain Wall System (Unitized, Low-E)	m2	28,000	—	—
14	AAC Block Partitions (200 mm)	m2	18,500	—	—
15	Granite Flooring — Lift Lobbies	m2	2,400	—	—
16	Screed & Topping — Office Floors	m2	34,000	—	—
17	Waterproofing — Raft & Basement	m2	5,800	—	—
18	Plastering — Internal Walls	m2	42,000	—	—
19	Paint — Interior (2 coats premium emulsion)	m2	42,000	—	—
20	Contingency (Provisional Sum)	LS	1	15,000,000	15,000,000