

Project: Construction of Industrial Warehouse G+1

Document: Industry Standards & Quality Control Protocols

1. International & Local Codes

- **Structural Design:** All concrete and steel works must comply with **ACI 318** (American Concrete Institute) and **ASTM** standards.
- **Local Regulations:** Construction must follow the **Building Control Authority (BCA)** bylaws for Lahore.

2. Safety & Health (HSE)

- **PPE Mandate:** No worker is allowed on-site without a hard hat, high-visibility vest, and steel-toed boots.
- **Fire Safety:** The warehouse must include a fire hydrant system and smoke detectors as per **NFPA 101** standards.
- **Scaffolding:** Any work above 2 meters height requires certified scaffolding and safety harnesses.

3. Quality Control (QC)

- **Slump Test:** Every concrete batch must undergo a slump test on-site to verify workability before pouring.
- **Curing:** All RCC elements must be water-cured for a minimum of **14 consecutive days**.
- **Material Testing:** Steel samples must be sent to an approved lab for tensile strength testing before use in the main structure.